

INSPECTIONS


All field inspections must be requested by the applicant. Inspections must be conducted as follows:

Tree Save Plans and Forest Conservation Plans without Planting Requirements

1. After the limits of disturbance have been staked and flagged, but before any clearing or grading begins
2. After necessary stress reduction measures have been completed and protection measures have been installed, but before any clearing and grading begin.
3. After completion of all construction activities, but before removal of tree protection fencing, to determine the level of compliance with the provision of the forest conservation.


Additional Requirements for Plans with Planting Requirements

4. Before the start of any required reforestation and afforestation planting
5. After the required reforestation and afforestation planting has been completed to verify that the planting is acceptable and prior to the start the maintenance period.
6. At the end of the maintenance period to determine the level of compliance with the provisions of the planting plan, and if appropriate, release of the performance bond.




SUPER SILT FENCE

NTS




TREE PROTECTION DETAIL

NTS



TREE PROTECTION FENCE - CHAIN LINK

NTS



ROOT PRUNING

NTS

McLaren ENGINEERING GROUP

601 East Pratt Street, Suite 302 Baltimore, Maryland 21202

T: (410) 243-4956 F: (410) 243-4956 www.mclaren.com

PROJECT

ARIS T. ALLEN BOULEVARD

RESIDENTIAL PLANNED DEVELOPMENT

(PART 1)

6TH ELECTION DISTRICT

CITY OF ANNAPOLIS, MARYLAND

TAX MAP GRID: 51E/8

STATE OF MARYLAND

4-18-14

SHEET TITLE

FOREST CONSERVATION

NOTES & DETAILS

GRADING PERMIT NO.: GRD 14-0006

PROJECT NO. 130003.01

SCALE AS SHOWN

DATE 4/28/2014

DRAWN BY JDS/CLW

CHECKED BY PVM/TJC

DRAWING NO.

FCP-4

63 of 63 SHTS