This note addresses Comment #1 of letter dated May 23, 2014 from Frank Biba, Chief - Environmental Programs, Department of Neighborhood and Environmental Programs.

Comment #1: The demonstration, as referenced in item 4 on page 3-6 of the Manual, shown on sheet 63 is insufficient. Please provide more detailed information. Please answer all the questions.

4. If the areas located in (1) through (3) above are within the proposed limits of disturbance, the applicant must demonstrate that: Steep slopes, Chesapeake Bay Critical Area, wetlands, floodplain and buffers are identified on the plan. It should be noted that all of these areas fall outside the LOD. There are no other priority areas or priority trees on the site. The proposed development activities avoid these priority areas. The existing recorded forest conservation easement is shown. Specimen trees and their critic al root zones have been identified. All of the areas on site under the criteria listed in 1 through 3 above are all outside the LOD and are being preserved. As such, no further demonstrations are required.

Nine (9) of the specimen trees (30" DBH and larger) are within the LOD. Items a-c below address these specimen tree concerns. a. All techniques for retention of these area have been exhausted

Opportunities for retention techniques are largely limited by the location of the specimen trees, the configuration of the site, and the layout of the platted subdivision. Appropriate methods will be used to preserve trees at the perimeter of the development, including root pruning and protection fencing.

b. Why these areas cannot be left undisturbed

These nine (9) trees are located within roadways and on lots of this previously platted and recorded subdivision. There is no opportunity to leave them undisturbed within the limits of the proposed development.

c. How reforestation will be accomplished, and, where on the site in priority areas, afforestation or reforestation will be located, if required (see Section 3.1.3 for explanation of afforestation and reforestation threshold requirements). No additional afforestation or reforestation is required, as shown by the Forest Conservation Worksheet. The proposed development exceeds the desired conservation threshold.

INSPECTIONS


All field inspections must be requested by the applicant. Inspections must be conducted as follows:

Tree Save Plans and Forest Conservation Plans without Planting Requirements

- 1. After the limits of disturbance have been staked and flagged, but before any clearing or grading begins
- 2. After necessary stress reduction measures have been completed and protection measures have been installed, but before any clearing and grading begin.
- 3. After completion of all construction activities, but before removal of tree protection fencing, to determine the level of compliance with the provision of the forest conservation.

Additional Requirements for Plans with Planting Requirements

- 4. Before the start of any required reforestation and afforestation planting 5. After the required reforestation and afforestation planting has been completed to verify that the planting is acceptable and prior to the start the maintenance period.
- 6. At the end of the maintenance period to determine the level of compliance with the provisions of the planting plan, and if appropriate, release of the performance bond.



45 DEGREES TO THE MAIN FENCE ALIGNMENT TO PREVENT RUNOFF FROM GOING AROUND THE ENDS OF THE SUPER SILT FENCE.


PROVIDE MANUFACTURER CERTIFICATION TO THE INSPECTION/ENFORCEMENT AUTHORITY SHOWING THAT GEOTEXTILE USED MEETS THE REQUIREMENTS IN SECTION H-1 MATERIALS.

REMOVE ACCUMULATED SEDIMENT AND DEBRIS WHEN BULGES DEVELOP IN FENCE OR WHEN SEDIMENT REACHES 25% OF FENCE HEIGHT. REPLACE GEOTEXTILE IF TORN. IF UNDERMINING OCCURS, REINSTALL CHAIN LINK FENCING AND GEOTEXTILE.


MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE MARYLAND DEPARTMENT OF ENVIRONMENT WATER MANAGEMENT ADMINISTRATION

SUPER SILT FENCE

STANDARD SYMBOL



TREE PROTECTION DETAIL



TREE PROTECTION FENCE FENCE WITHIN I' OF TRENCH LINE —TRENCH WITHIN I' OF LIMIT OF DISTURBANCE LINE CRITICAL ROOT ZONE 1. Retention Areas to be established as part of the forest conservation plan review process.

2. Boundaries of Retention Areas to be staked, flagged and/or fenced prior to trenching.

3. Exact location of trench should be identified.

4. Trench should be immediately backfilled with soil removed or organic soil.

5. Roots should be cleanly cut using vibratory knife or other acceptable equipment. Source: Adapted from Steve Clark & Associates/ACRT, Inc. and Forest Conservation N Root Pruning Figure D-1

D-2

ROOT PRUNING

NTS

COPYRIGHT © 2014, McLAREN ENGINEERING GROUP

I BOULEVARD JED DEVELOPN 26 - 31, 47 & 48

ALLEN I PLANNE

RIS

SHEET TITLE

CONSERVATION S & DETAILS

OREST

130003.0

JDS/CLW

A IDE PA

48

26

O

THESE PLANS ARE BASED UPON PLANS TITLED 'ARIS ALLEN BOULEVARD, LLC MIXED

RESIDENTIAL' CREATED BY BOWMAN CONSULTING, PORTIONS OF WHICH ARE USED HEREIN.

PROJECT NO.

CHECKED BY